

PROJECT PROFILE

Ledyard

LOCATION

Kossuth County, IA

START DATE

September 2021

END DATE

Q4 2022



SCOPE

CSA CONTRACT

- Full engineering
- Civil works with cement stabilized roads and drain tile under the entire project
- Foundation construction with geopiers in a few locations
- Collection installation
- Substation construction
- O&M building construction
- Installation of 46 Ea Vestas V150 4.3 MW turbines, five-section towers with multi-part nacelles requiring assembly on the ground and tower wiring